



Work Quote

Big Dog Roofing & Construction

Mt Pleasant, Texas
 Mobile : 903-387-4708
 Office : 903-243-9335
john@bigdogroofing.net

ESTIMATE NO. 7450
 DATE February 17, 2021
 CUSTOMER ID **Revised Annex**
 EXPIRATION DATE **2/23/2021**

TO:

Titus County
105 W 1st St
 Mt Pleasant
 75455
Annex Labs / Courtroom B Labs

SALESPERSON	JOB	PAYMENT TERMS	Expiration Date
John McDermott - Owner -	Annex M/W Labs/Courtroom B Labs	Check Only by Draws	2/23/21

QUANTITY	DESCRIPTION	UNIT PRICE	LINE TOTAL
	Minor Interior Demo and Construction		
Annex Mens/Womens Labs	Minor Demo to existing vanities in both Mens and Womens Labs.		
	R&R both dual vanities (demo)		
	R&R 4 sinks replace with wall mounted ADA sinks (cust supply fixtures)		
	Plumbing for both Labs to equal 4 sinks		
	Mount Sinks to existing tile wall. Labor and Material		
Courtroom B Mens / Womens Labs	Minor Demo to existing vanities in both Mens and Womens Labs		
	Minor Construction, removing sheetrock and apply new , reason is to install a backer stud to mount the wall maunted ADA sinks.		
	Tape,texture and paint to match existing color		
	Plumbing for both Labs to equal 2 sinks (cust supply fixtures)		
	Labor and Material install new ADA wall mounted sinks		
NOTE:	All Labor,Material,Dumpster,Permits and Insurance is included in price		
NOTE:	Big Dog Roofing & Construction holds a Million Dollar General Limited Liability Insurance and license LLC company		

Total	\$3,350.00
Tax	-
Total	\$3,350.00

Estimate prepared by: John McDermott - Owner

This is a estimate on the goods named, subject to the conditions noted below:
 (Describe any conditions pertaining to these prices and any additional terms of the agreement.
 You may want to include contingencies that will affect the estimate.)

To accept this estimate, sign here and return: *John McDermott*

Thank you for your business and have a blessed day ... Proverbs 3 : 5-6 Trust in the Lord with all your heart and lean not on your own understanding; in all your ways acknowledge him, and he will make your paths straight.

Commissioners' Court approved 3-8-21 with one pre-completion draw and final draw at completion.
BK